

# SPP RTO Missouri PSC Presentation

November – 2016 Paul Suskie – EVP and <u>GC, SPP</u>

### Agenda

- Integrated Marketplace Updates
- Tariff Attachment Z2 Credits
- Regional Cost Allocation Review (RCAR) Update
- Regional and Interregional Planning Updates






### Integrated Marketplace Update

Bruce Rew, PE

Vice President, Operations


### SPP Integrated Marketplace Update

- Marketplace Statistical Information
- Marketplace Wind Peak and Penetration
- Integrated Marketplace Savings





### Dispatch by Fuel Type






### Marketplace Operational Highlights

- 3rd Quarter Peak Load of 50,622 on July 21, 2016
  - New market footprint record
  - Largely due to addition of Integrated Systems October 2015
- Total of 12,400 MW of installed and operational wind capacity to date
  - As of October 1<sup>st</sup>, an additional 3,300 MW of wind registered
    - A portion of that has begun the commissioning/testing phase
- Additional 140MW of operational solar capacity
  - Total of 190MW currently installed and operational capacity
  - 25 MW registered, not yet operational



### July – September 2016






### Integrated Marketplace Savings

- Market continues to provide savings even with extremely low natural gas prices below \$2
- First year net savings calculated to be \$380 million
- 2015 annual net savings calculated to be \$422 million
- At the July RSC Staff projected over \$1 Billion in savings by the 75<sup>th</sup> Anniversary
- At the end of September the savings amount was:

\$1,000,009,648









# Questions

Integrated Marketplace





Z2 Update

# Significant FERC Dockets Original Obligations

- Rulemaking (RM02-1): Established national policy for revenue credits from transmission service for Generator Interconnection customers that bear upgrade costs [FERC ORDER 2003]
- <u>ER05-109</u>: Created revenue credits to compensate entities in SPP that bear directly assigned service upgrade costs (Attachment Z)

#### **Clarifying Filings at FERC**

- <u>ER08-746</u>: Attachment Z was separated into Z1 Aggregate Study Procedures and Z2 Revenue Crediting Procedures (Credits)
  - Credits based upon NITS & PTP service that could not be provided "but for" the existence of the upgrade
  - Included credits for Project Sponsors
  - Recognized that a Network Upgrade may also provide benefits for service in the opposite direction
- ER13-1914: Clarifications to Revenue Crediting
  - Clarified the funding of credits and the distribution of credit revenue for Creditable Upgrades under the Tariff
  - Included provisions that were designed to reduce the number of Creditable Upgrades over time



### Attachment Z2 Background

- SPP Tariff Attachment Z2 provides a process to compensate (via revenue credits) those Upgrade Sponsors who pay for upgrades that are subsequently used by transmission customers
- Unpaid credit amounts occur as early as 2008
  - FERC approved a waiver of the Tariff to permit settlement of the 2008-2016 charges and credits under Attachment Z2



### Z2 Implementation – Key Dates

Begin historical processing	Feb. 16
Network direct assignments to fund CPOs	Apr. 28
Provided long-term CPOs and Schedule 11 impacts	July 12
Posted initial settlements for historical period	Sept. 13
Summary and detailed results for each company	
Input data	
Payment plan election	Oct. 7
Post updated settlements for historical period	Oct. 19
Provide overall total on payment plan	Oct. 19
Invoice for historical period and September 2016	Nov. 3



### ATRRs Compared to Annual Credit Payment Obligations (CPOs) (\$millions)

Year	Total ATRR (Sch. 9+11)	Total CPO of LT Service	Percentage of ATRR
2008	\$ 571.8	\$ 0.1	0.0%
2013	\$ 1,175.0	\$ 26.0	2.2%
2018	\$ 2,163.5	\$ 68.0	3.1%
2023	\$ 2,220.0	\$ 38.5	1.7%
2028	\$ 2,070.1	\$ 34.2	1.7%
2033	\$ 1,919.8	\$ 21.9	1.1%
2038	\$ 1,769.6	\$ 4.1	0.2%
2043	\$ 1,619.3	\$ 1.4	0.1%





# RARTF RCAR II Presentation

July 5, 2016

# OATT Requirements



### SPP Tariff Requirement – Reviews.

- The Transmission Provider shall review the reasonableness of the regional allocation methodology and factors (X% and Y%) and the zonal allocation methodology at <u>least once every</u> three years in accordance with this Section III.D.
- The Transmission Provider and/or the Regional State Committee may initiate such review at any time.
- Any change in the regional allocation methodology and factors or the zonal allocation methodology shall be filed with the Commission.



### **RARTF Members**

Chairman Steve Stoll	Missouri Public Service Commission
Vice-Chairman Richard Ross	American Electric Power
Commissioner Shari Feist Albrecht	Kansas Corporation Commission
Commissioner Lamar Davis	Arkansas Public Service Commission
<b>Board Member Steve Lichter</b>	Nebraska Power Review Board
Bill Grant	Southwest Public Service
Bary Warren	South Central MCN/GridLiance
Philip Crissup	Oklahoma Gas & Electric
Harry Skilton	SPP Board of Director



# RCAR II RESULTS



### RCAR II—B/C Ratio

	Present Value of 40-yr Benefits for the 2015-2054 Period (2016 \$million)  Capital								PV of 40-yr ATRRs (2016 \$million)					B/C Ra	Gap to Reach B/C Ratio of 0.8 (2016 \$million)				
		A !	Capacity	N 40'41'		Benefit					Savings	3	2,6		46				
		Avoided or	from	Mitigation of Trans-	Assumed Benefit of		Increased Wheeling	Marginal	Reduced	Reduced	from Reduced		Before PtP and	PtP and	After PtP and				
		Delayed	Reduced		Mandated	Public	Through	Energy	Cost of		Minimum		MISO	MISO		Ве	n efit/		
		Reliability	On-Peak	_	Reliability	Policy	and Out	Losses			Required	1	Revenue		Revenue		Cost		Levelized
	Savings	Projects	Losses	Costs	Projects	Goals	Revenues	Benefits	Events	Probability	Margin	Benefits	Offset	Offset	Offset	L	Ratio	TOTAL	Real
AEP	\$1,216	\$20	\$87	\$207	\$965	\$0	\$133	\$59				\$2,686	\$1,654	\$121	\$1,533		1.75	\$0	\$0.0
CUS	-\$33	\$0	\$0	\$14	\$53	\$0	\$5	\$2				\$42	\$76	\$5			0.59	\$15	\$0.9
EDE	-\$25	\$0	\$0	\$24	\$83	\$0	\$12	\$0				\$95	\$126	\$9	\$117		0.81	\$0	\$0.0
GMO	\$174	\$1	\$3	\$38	\$180	\$0	\$19	-\$2				\$412	\$207	\$15			2.15	\$0	\$0.0
GRDA	\$82	\$0	\$1	\$19	\$70	\$0	\$13	-\$6				\$179	\$114	\$8			1.68	\$0	\$0.0
KCPL	\$642	\$1	\$6	\$76	\$308	\$0	\$37	\$51				\$1,122	\$407	\$29		_	2.97	\$0	\$0.0
LES	\$115	\$0	\$1	\$19	\$64	\$0	\$8	\$15				\$223	\$106				2.27	\$0	\$0.0
MIDW	\$76	\$0	\$11	\$8	\$93	\$0	\$5	-\$3				\$190	\$71	\$5	-	1	2.89	\$0	\$0.0
MKEC	\$60	\$0	\$17	\$13	\$171	\$0	\$14	\$30		Not Monetize	ed	\$306	\$259	\$20			1.28	\$0	
NPPD	\$158	\$1	\$53	\$58	\$275	\$0	\$38	-\$9				\$574	\$404	\$29	-		1.53	\$0	
OGE	\$1,428	\$2	\$65	\$131	\$635	\$0	\$66	-\$64				\$2,262	\$838				2.91	\$0	
OPPD	\$24	\$1	\$3	\$48	\$150	\$0	\$23	\$9				\$257	\$320	\$23		_	0.87	\$0	
SEPC	\$83	\$0	\$12	\$9	\$159	\$0	\$8	\$11				\$283	\$82			4	3.73	\$0	\$0.0
SPS	\$3,537	\$12	\$357	\$115	\$1,024	\$0	\$90	-\$13				\$5,122	\$1,402	\$102			3.94	\$0	
UMZ	\$281	\$1	\$47	\$96	\$595	\$0	\$55	\$191				\$1,266	\$397	\$45			3.60	\$0	7 - 1 -
WFEC	\$159	\$0	\$77	\$34	\$222	\$0	\$20	\$56				\$568	\$295	\$21			2.08	\$0	\$0.0
WR	\$996	\$1	\$5	\$105	\$710	\$0	\$94	\$100				\$2,011	\$1,002	\$73	\$930	L	2.16	\$0	\$0.0
TOTAL	\$8,974	\$41	\$743	\$1,014	\$5,759	\$0	\$641	\$427				\$17,599	\$7,760	\$579	\$7,180		2.45		



### Work with Deficient Zone

- City Utilities of Springfield (CUS)
  - Staff has worked with CUS to address remedy options
  - CUS has expressed interest in Remedy #2
    - Issuance of NTCs for selected new upgrades
  - CUS will be focused on upcoming planning processes
    - 2017 ITP10 (January 2017)
    - Seams Study with AECI (End of 2016)
    - Seams Study with MISO (TBD)
  - Another option would be for the SPP BOD to direct a High Priority Study for the CUS area



### Other Zones

- Two additional zones are above the 0.8 threshold but below the 1.0
  - OPPD and Empire
  - RARTF Report and Lessons Learned both stated that zones above the threshold but below 1.0; "that this analysis should be used and considered as a part of SPP's transmission planning process in the future."
  - Staff will work with both in upcoming planning processes to address needs and solutions for OPPD and Empire





# 2017 ITP10 Overview

October 24th, 2016

**RSC** 

### 2017 ITP10 Futures

• Future 1 – Regional Clean Power Plan Solution

• Future 2 – State Level Clean Power Plan Solution

• Future 3 – Reference Case



# Needs and Project Evaluation

2017 ITP10






# ITP10 Needs in CUS and Empire Area

- Neosho Riverton 161 kV FLO Neosho Blackberry 345 kV
  - Empire District
  - West to east power transfer limitation in southeast KS
- Brookline 345/161 kV transformer #1 FLO Brookline 345/161 kV transformer #2
  - City Utilities of Springfield
  - Bulk power transfer to serve load in the city of Springfield
- Both of these needs are chronic operational issues as well
- Solutions for these needs are currently being analyzed



# 2017 ITP10 Needs in CUS and Empire






# Project Portfolios

2017 ITP10





### Future 1 Portfolio – Regional CPP






30


<sup>\*</sup> One project is included in both the economic and reliability portfolios

### Future 2 Portfolio – State CPP






### Future 3 Portfolio – Reference Case





### Multi-Variable Portfolio






### Multi-Variable Portfolio

- Certain transmission issues identified under out of scope criteria were posted for informational purposes
- This was done to allow for submittal and further evaluation of projects that may support SPP initiatives but are not addressing official Needs per the ITP10 Scope
  - RCAR II
  - Seams
  - Operational issues
- Current target areas for potential project recommendations
  - Eastern Seams
    - Southeast Kansas Southwest Missouri
    - Northeast Oklahoma Northwest Arkansas
  - Texas Panhandle
    - SPS North to South



### **Next Steps**





# Questions

ITP-10 Planning Process





# Seams Update

October 24, 2016

**RSC** Meeting



75

### Associated Electric Cooperative Inc.


A Touchstone Energy® Cooperative

# SPP-AECI JCSP



### 5 Focus Areas 2016 SPP-AECI JCSP Target Areas

- Northeast
   Oklahoma
   potential overloads
   and voltage issues
- Brookline potential overloads and voltage issues
- Norton & Georgetown potential low voltage issues
- Wheaton area potential upgrades
- Mid-Missouri potential low voltages





### **Next Steps**

- October 4<sup>th</sup>, 2016
  - Target Area Models posted to TrueShare
  - Target Area needs posted to TrueShare
  - Solution ideas were requested from stakeholders
- November 7th, 2016
  - Deadline for stakeholder developed solutions to be submitted into the process
- December 2016
  - Issue draft study report
- Ongoing
  - SPP & AECI staff developing solutions







# SPP-MISO CSP



### Interregional Order 1000




- ✓ Completed 2014 CSP in June 2015
- Received final FERC order on compliance on April 6, 2016
- ✓ Have begun 2016 CSP

- Process
  Improvements
- ☐ Interregional "Overlay" Study

### Southeastern Regional

TRANSMISSION PLANNING


- Received final FERC order on compliance on April 12, 2016
- ✓ SPP-SERTP meeting held on June 30, 2016 to review respective regional transmission plans
- ☐ No interregional projects have been submitted or identified for evaluation







### 2016 SPP-MISO CSP Needs



NEED ID	CONSTRAINT
1	Rugby WAUE-Rugby OTP Tie
2	Hankinson - Wahpeton 230kV FLO Jamestown - Buffalo 345kV
3	Sub3 - Granite Falls 115kV Ckt1 FLO Lyon Co. 345kV Ckt1
4	Sioux Falls - Lawrence 115kV FLO Sioux Falls - Split Rock 230kV
5	Northeast - Charlotte 161kV FLO Northeast - Grand Ave West 161kV
6	Neosho - Riverton 161kV FLO Neosho - Blackberry 345kV
7	Brookline 345/161kV Ckt 1 Transformer FLO Brookline 345/161kV Ckt 2 Transformer



### Request for solutions

- October 3<sup>rd</sup>, 2016
  - Needs posted to SPP's TrueShare
    - Background presentation and maps
  - Solution ideas were requested
  - SPP and MISO regional models are available for project testing
- November 30<sup>th</sup>, 2016
  - Deadline for stakeholder developed solutions to be submitted into the process
- Ongoing
  - 2016 SPP-MISO Joint Model Build



### Schedule

#### SPP-MISO CSP Tasks

- Develop and finalize scope document for CSP study August 2016
- Develop detailed schedule for CSP study August 2016
- 3. Economic Evaluation
  - Model Development November 2016
  - Determine needs list from regional studies August 2016
  - Solution Development November 2016
  - Solution Evaluation and Robustness Testing February 2017
  - Reliability No Harm Analysis March 2017
  - Determine interregional cost allocation March 2017
- Coordinated Reliability Assessment March 2017
- Draft Coordinated System Plan study report April 2017
- Regional Evaluation and Cost Allocation (if needed)





# Questions

